

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00454-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1970
CONSERVATION DIVISION
Wichita, Kansas
7-31-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Midwestern Supply Co., Inc.

Complete Address 710 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name McCormell Well No. 1

Location SW NW SE Sec. 35 Twp. 4 Rge. (E) (W) 20

County Phillips Total Depth 3719'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 4:30 P Day 29 Month 7 Year 1970

The above well was plugged as follows:

Total Depth 3719' 8 5/8 csg set at 242' cwc

5 1/2 csg set at 3419' cw 100 sk cmt.

5 1/2 csg PBTD 3385' with top perf. (3355')

Set plug 3300 poured 25' sd & dumped 5 sk cmt with dump bailer.

Cutoff and recovered 2780' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 10 sk gel W/5 sk hulls - 70 sk poz 6% - 15 sk gel - plug and 55 sk poz 6%. Max. pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 7/31/70

INV. NO. 2313-W