

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1960
CONSERVATION DIVISION
Wichita, Kansas
10-18-60

15-147-00140-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Phillips

Location: CSE NW Sec. 25 Twp. 4 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3480

I have this date completed supervision of plugging of:

Lease Name: Lynch Well No. A-1

Operator's Full Name: R. W. Rine Drg Co

Complete Address: 420 ~~xxx~~ Union Center Wichita, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10:30 AM Day 10 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 224' circulated with cement - 5 1/2" 3462' with 100 sax cement.

PB to 3141' perforated 3125'

Filled with sand to 3115' set 4 sax cement with dump bailer, pulled

2376' 5 1/2" - filled hole with heavy mud to 220', set rock and 20 sax

cement, heavy chunk mud to 40', set rock and 10 sax cement to bottom

cellar.

Signed: *Leon Perry*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 10/31/60
INV. NO. 2132-W