

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-147-20,270-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name David Oil Co. Inc.

Complete Address Box 428 Logan, Kansas 67646

Lease Name States Well No. 1

Location SW-SE-SW Sec. 26 Twp. 4 Rge. 20 (East) (West)

County Phillips Total Depth 3350'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing

Address Chase, Kansas License No. 683

Operation Completed: Hour: 1:00PM Day: 9 Month: 6 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" set @ 245 1/2' w/175 sy common - 4 1/2" @ 3349' w/350x
50/50 pozmix & 200 sy common - Reqs 318 3/4 93
Rec. overed 2016' - cut plug @ 3100' & 50' sand & 4 sy emt
Ordered 140 sy 50/50 pozmix, 6 3/4 gal 3% CC; 25 gal 5 hulls &
8 5/8" plug: Pumped in 4 hulls -> 13 gal -> 1 hull -> 70 emt ->
12 gal -> Rel. plug -> 70 emt. Max P.S.F. 300 #

Amount of Surface Casing: 245 1/2'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 7-22-82

INV. NO. 658-W