

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00721-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1962
7-16-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bankoff Oil Co
Complete Address: 1312 Eisenhour Great Bend, Kans
Lease Name Gillam Well No. 1
Location SE NE SE Sec. 26 Twp. 4 Rge. (E) (W) 20
County Phillips Total Depth 3344
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Pipe Pullers Inc
Address: Great Bend, Kansas License No. 462
Operation Completed: Hour 2:30PM Day 11 Month 7 Year 62

The Above well was plugged as follows:

~~8 5/8" 234' circulated with cement - 4 1/2" 3344' with 100 sax cement. PB to 3218' - perf 3168'. Filled with sand to 3150', set 3 sax cement with dump bailer - pulled 2100' 4 1/2" to 550', circulated hole through 4 1/2" with heavy drilling mud, displaced 20 sax cement through 4 1/2" at 550', heavy mud to 200', displaced 20 sax cement through 4 1/2" - heavy mud to 30', filled to bottom cellar with cement.~~

Mudding and cementing by Pipe Pullers Inc. pump truck .

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 7/17/62
INV. NO. 5372-W

Signed: [Signature]
Well Plugging Supervisor