

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

15-137-20208-0000

Give All Information Completely
Make Required Affidavit

COUNTY Norton SEC. 13 TWP. 4S RGE. 25W E/W
Location as in quarters or footage from lines:

Locate Well
correctly on above
Section Platt.

NE SE NW
Lease Owner F & M Oil Company, Inc.
Lease Name L. Smith Well No. #1
Office Address 422 Union Center Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 10-1-81
Plugging completed 10-7-81
Reason for abandonment of well or producing formation

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top bottom T.D. 3980'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	274'	none
				4-1/2"	3847'	2253'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Moved in on location, got 11" stretch, plugged off bottom with sand to 3700' and set 4
sacks cement. Shot pipe @3286', 3144', 3000', 2880' 2677', 2475' and 2270' Pulled
a total of 56 joints of casing. Plugged well with 15 sacks gel, 3 sacks hulls, 70 sacks
cement, 12 sacks gel, 8-5/8" plug, and 60 sacks 50/50 pos, 6% gel, Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature)

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 19 81

My Commission expires:



RECEIVED
Notary Public
STATE CORPORATION COMMISSION
16-15-81
OCT 15 1981

CONSERVATION DIVISION
Wichita, Kansas