

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20,839-06-00

LEASE NAME Lieber 33

WELL NUMBER 1

SPOT LOCATION SW/4 NE/4 SW/4

SEC. 33 TWP. 4S RGE. 26 (E)/dr/(W)

COUNTY Decatur

Date Well Completed 1/24/89

Plugging Commenced 1/24/89

Plugging Completed 1/24/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Felmont Oil Corporation

ADDRESS P. O. Box 2266, Midland, Texas 79702

PHONE # 915, 682-5231 OPERATORS LICENSE NO. 3916

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas - Gilbert Scheck

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4,060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210.90	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 3990' w/20 sx cement; 2nd Plug @ 2200' w/20 sx cement;

3rd Plug @ 1400' w/100 sx cement & 1 sx of Floseal;

4th Plug @ 250' w/40 sx cement; 5th Plug @ 40' w/10 sx cement;

15 sx cement in rathole

205 sx 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302

Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF Texas COUNTY OF Midland, ss.

Kenny C. Smith

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kenny C. Smith

(Address) P. O. Box 2266
Midland, Texas 79702

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1989

Sherry Roberts

Notary Public - State of Texas

My Commission expires: Commission Expires 8-13-89

Notary Public