

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2004

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

15-035-20852-00 00
API NUMBER 15-035-20852 0000

LEASE NAME Roland L Lewis (Twin)

WELL NUMBER 1 # ~~1~~ ^{KCC} ₃₈₁ ^{10/18/04}

4850 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 30 TWP. 31 RGE. 7 (E) or (W)

COUNTY Cowley ^{KCC} _{10/18/04}

Date Well Completed 8/13/75 ¹²⁶

Plugging Commenced 09/30/04 ^{10/6}

Plugging Completed 10/06/04

CONSERVATION DIVISION
WICHITA, KS
LEASE OPERATOR Braden Petroleum & Well Plugging

ADDRESS PO Box 282 Burden, KS 67019

PHONE# (620) 438-2856 OPERATORS LICENSE NO. 32475

Character of Well Gas SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 22 2004 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Layton Stalwaker Depth to Top 2129 1725 Bottom 2139 1745 T.O. 2215

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| Layton | Water | 2129 | 2139 | 8 7/8 | 212' | 0' |
| Stalwaker | Water | 1725 | 1745 | | | |
| | | | | 2 7/8 | 2211' | 465' |
| | | | | 2 7/8 | 1838 | 395' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.

Run work string 1 1/2" tubing inside 2 7/8" tubing to 2139' pumped 10 sk cement bottom run 1 1/2" tubing inside 2 7/8" tubing in SWD to 1745' pumped 10 sk cement on bottom pulled 1 1/2" tubing out shot off 2 7/8" tubing 1 1/2" string 465' laid out shot off 2 7/8" string 2 7/8" tubing 395' laid out - run 1 1/2" tubing inside 2 7/8" surface to 310' pumped 105 sk on to 470' to the surface laid out 1 1/2" tubing top of surface with cement TK No 04/427

Name of Plugging Contractor Braden Petroleum & Well Plugging License No. 32475

Address PO Box 282 Burden, KS 67019

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Braden Petroleum & Well Plugging

STATE OF Kansas COUNTY OF Cowley, ss.

(Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) James L. Brach

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 2004
PATRICIA C. BRADEN

NOTARY PUBLIC

Patricia C Braden
Notary Public

STATE OF KANSAS
My Commission Expires: 2-21-2006
MY APPT. EXPIRES