

CONSERVATION DIVISION
WICHITA STATE OFF. BUILDING
130 S MARKET ROOM 2078
WICHITA KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-001 ⁰¹⁸⁷¹⁻⁰⁰⁻⁰⁰ ~~Filed 1961~~

LEASE NAME McEndree

WELL NUMBER 2

3390 Ft. from S Section Line

2440 Ft. from E Section Line

SEC. 14 TWP. 25 RGE. 19 (E) of KMX

COUNTY Allen

Date Well Completed 1961

Plugging Commenced 9-3-04 ¹⁰⁷⁵⁻⁰⁴

Plugging Completed 9-3-04

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Consa Div
office within 30 days.

CONSERVATION DIVISION
WICHITA, KS

LEASE OPERATOR Donald & Jack Ensminger

ADDRESS 1446-3000 St. Moran, Kansas 66755-3949

PHONE# (620) 496-2300 OPERATORS LICENSE No. 6137

Character of Well Oil Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-3-04 (date)

by Thomas Welsh (KCC District Agent's Name):

Is ACO-1 filled? Yes If not, is well log attached? No

Producing Formation Bartlesville Depth to Top 830 Bottom 855 T.D. 855

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Bartlesville	Oil	830	855	2"	840'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran 855' of 1" inside 2" pumped 60 sx cement to surface

Ran 250' of 1" outside 2" pumped gel & cotton seed hulls

until circulation appeared pumped 30 sx cement to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Donald & Jack Ensminger License No. 6137

Address 1446-3000 St. Moran, Kansas 66755


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Donald Ensminger

STATE OF Kansas COUNTY OF Allen, ss.

Owner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct; so help me God.

(Signature) Donald Ensminger

(Address) 1446-3000 St Moran, KS 66755



My Commission Expires: 4-24-07 My Address SUBSCRIBED AND SWORN TO before me this 12th day of Oct, 2004

Marianne McVey
Notary Public