

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22038-00-00
Spot: SESWSW Sec/Twnshp/Rge: 32-30S-14W
393 feet from S Section Line, 4531 feet from E Section Line
Lease Name: BIBB Well #: 1
County: BARBER Total Vertical Depth: 4573 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 4571 WITH 200 SX CMT
SURF Size: 8.625 feet: 312 WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2004 12:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 3775' & DUMP 5 SX CMT ON TOP OF SAND. FREE POINT & PULL CASING TO 700'. PUMP 10 SX GEL & 50 SX CMT. PULL CASING TO 340' & SPOT 50 SX CMT. PULL CASING TO 40' & CIRCULATE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2004 1:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3775' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3828	3832		

RECEIVED
OCT 18 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2840' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

(TECHNICIAN)

Form CP-2/3