

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20630-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 23-34S-21W  
1650 feet from N Section Line, 330 feet from W Section Line  
Lease Name: BARBY Well #: 5-23  
County: CLARK Total Vertical Depth: 5510 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N. TYLER  
WICHITA, KS 67212

COND Size: 20 feet: 85 WITH 350 SX CMT <sup>08</sup>  
II Size: 8.625 feet: 842 WITH 650 SX CMT \$179  
PROD Size: 5.5 feet: 5503 WITH 300 SX CMT  
SURF Size: 13.38 feet: 330 WITH 700 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2004 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Revd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 100# HULLS. PLUG AT 875' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT. MUD SPACER TO 4290'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/08/2004 5:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5403'. PUMP 800# HULLS & 50 SX CMT. 1ST PLUG LOAD HOLE WITH MUD & SPOT 50 SX CMT AT 875'. 2ND PLUG PULL TO 400' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5409	5413		
4280	4286		

RECEIVED  
OCT 18 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2677' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Steve Middleton*

(TECHNICIAN)

INVOICED

DATE 10-18-04

INV. NO. 2005060669

Form CP-13