

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21632-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 14-35S-12W
3720 feet from S Section Line, 520 feet from E Section Line
Lease Name: GOTTSCH-PETERMANN Well #: 4
County: BARBER Total Vertical Depth: 4925 feet

Operator License No.: 6006
Op Name: MOLZ OIL COMPANY
Address: 19159 S.W. CLAIRMONT
KIOWA, KS 67070

CIBP Size: feet: 4700 WITH 2 SX CMT
PROD Size: 5.5 feet: 4925 WITH 150 SX CMT
SURF Size: 8.625 feet: 346 WITH 300 SX CMT

06
\$160

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2004 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 370' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2004 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID CASING DOWN. RUN 2 7/8" TUBING IN TO SPOT PLUGS THROUGH. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4843	4906		

RECEIVED
OCT 18 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3250' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICE

DATE 10-18-04

INV. NO. 2005060672

Form CP 2/3