

6 031315

1-8

275 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,675 -00-00
230' N C
W/2 W/2 SE SEC. 14, T 4 S, R 27 W/E

TECHNICIAN'S PLUGGING REPORT

1550 feet from S section line
2310 feet from E section line

Operator License # 4712

Lease Name Shimmick Well # B-1

Operator: Taylor Brown Operating Inc. County Decatur
Name & Address: 459 S. Alcott
Denver, Colorado 80219

Well Total Depth 3730 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 8 Month: Jan Year: 19 90

Plugging proposal received from Mike

(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 329' w/240 sks cwc. 4 1/2" set at 3639' w/250 sks. Order sand and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 2% diel 500# hulls. Allied Cement Co. Larue water truck. Wireline to anhy.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15PM Day: 8 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom back to 3450' w/4 sks common cement on sand w/bailer. Five shots recovered 1200 of 4 1/2" casing. Squeezed 8 5/8" w/225 sks cement blend w/500# hulls mixed into max psi 300#. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JAN 26 1990 1-26-90

Remarks: Four empty cement paper sacks and residue of cement slurry was at location. (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

FEB 08 1990

DATE

INV. NO. 27362

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow