

6 031316

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,519-00-00

SE SW SE, SEC. 14, T. 4 S, R 27 W/EX

330 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
4712

Operator License # _____

Lease Name Schimmick Well # 2

Operator: Taylor Brown Operating Inc.

County Decatur 120.35

Name & Address 459 S. Alcott

Well Total Depth 3703 feet

Denver, Colorado 80219

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: _____ PM Day: 8 Month: Jan Year: 19 90

Plugging proposal received from Mike

(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 287' w/200 sks. 4 1/2" set at 3679 w/300 sks. Perf 3495 -99.

Order sand and common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 2% dicel
500# hulls. Allied Cement Co. Larue water trucks. Wireline to anhy.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00PM Day: 8 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom back to 3450' w/4 sks common cement on sand

w/bailer. Five shots recovered 1300' of 4 1/2" casing. Squeezed 8 5/8" w/225 sks
cement blend to max psi 500#. Close in psi 300#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1990 1-26-90
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

File S.

INVOICED
DATE FEB 03 1990
INV. NO. 27365