

To: **6 031314**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT
4712

Operator License # _____
Taylor Brown Operating Inc.
Operator: _____
Name & Address: 459 S. Alcott
Denver, Colorado 80219

1-8 276 R
API NUMBER 15- 039-20,467-00-00
SE SE SW 14 4 27
_____, SEC. _____, T _____, S, R _____ W&E
330 feet from S section line
2970 feet from E section line
Lease Name Shimmick Well # 1
County Decatur 119.80
Well Total Depth 3686 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050
Address Chase, Ks.

Company to plug at: Hour: PM Day: 8 Month: Jan Year: 19 90

Plugging proposal received from Mike
(company name) Kelso Casing (phone) _____

were: 8 5/8" set at 250 cwc. 4 1/2" set at 3685' w/250 sks. Perf 3501-5. Order sand and
common cement. Pull pipe. Order 225 sks 65/35 poz 10% gel 2% dicel 500# hulls. Allied
Cement Co. Larue water trucks.
Wireline to anhy.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 8 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom back to 3450' w/4 sks cement on sand w/
bailer. Five shots recovered 1200' of 4 1/2" casing. Squeezed 8 5/8" w/225 sks cement blend
w/500# hulls mixed into max psi 500#. Close in psi 300#. Plug complete

Remarks: Four empty cement paper sacks and residue of cement clurry was at location
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED
DATE FEB 07 1990
INV. NO. 27363

John S

Signed *Carl Goodrow*
(TECHNICIAN)
Carl Goodrow

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1990
CONSERVATION DIVISION
Wichita, Kansas
1-26-90