

12-8

6 031305

API NUMBER 15-039-20104-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SW, SEC. 4, T 4 S, R 27 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Kasper Well # 1

Operator: Okmar Oil Co.

County Decatur 122.82

Name & Address Box 723

Well Total Depth 3779 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour PM Day: 8 Month: Dec Year: 19 89

Plugging proposal received from Bob Grant

(company name) Okmar (phone)

were: 8 5/8" set at 288' cwc 4 1/2" set at 3779' w/175 sks. Perf 3576' - 3662'.

Squeeze from 2028' to 2701 w/250 sks. Packer cemented in at 2479'. Loc set at 3513'. Shot at 1475 (perf). Order 225 sks 65/35 poz 10% gel 2% dicel 500# hulls. Halliburton Cement Co.

Larue water trucks OWS rig.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00PM Day: 8 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 2438' tagged fish. Circulated cement blend to surface. Squeezed 4 1/2" casing w/total of 85 sks 400# hulls to max psi 600#. Close in psi 600#. Squeeze backside w/140 sks 100# hulls to max psi 300#. Close in psi 150#. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

JAN 17 1990

1-17-90 CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED JAN 24 1990

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

DATE

INV. NO. 27137 12-8 FEB 09 1990