

6 010154

15-039-20736-00-00

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 039- 20736

NE, SEC. 3, T. 4 S, R 27 W

330 feet from N/E section line

990 feet from A/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Tilden Well # 1

Operator: Diamond Shamrock Exp. County Decatur

Name & Address RT. 1 Box 23

Well Total Depth 4010 130.33 feet

Canadian Texas

Conductor Pipe: Size \_\_\_\_\_ feet

79014

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Diamond Shamrock Exp. License Number 9123

Address same

Company to plug at: Hour: 1:PM Day: 25 Month: 6 Year: 19 84

Plugging proposal received from Pete Coates

(company name) Diamond Shamrock (phone) 806 323-5307

were: order 210 sx. cement 50/50 permix 6% Gel. (no c.c. request)

1 sx hulls. 1. 8 5/8 plug 1 sx flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2629 Anhydrite 2142-85 Arbuckle. 3958

Dakota 1450 Plugging Proposal Received by Dale F. Batthagon (TECHNICIAN)

1179 = 1480

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None None

Operations Completed: Hour: 9:15 Day: 25 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3960 for 30 mi.

RECEIVED  
STATE CORPORATION COMMISSION  
7-9-84  
JUL 09 1984

25 SX @ 3960

25 SX @ 2150

100 SX @ 1480 mixed with 1 sx flow seal.

40 SX @ 350 dumped 1 sx hulls. pushed plug to 40'

10 SX @ 40

Remarks: 10 SX Rat Hole (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

Cemented by Halliburton Signed Dale F. Batthagon (TECHNICIAN)

INV. NO. 2386

FORM CP-2/3 Rev. 01-84

July 6 1984