

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00958-00-00
Spot: CNWNWNE Sec/Twnshp/Rge: 36-4S-20W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: SLINKER Well Number: 401
County: PHILLIPS Total Vertical Depth: 3315 feet

Operator License No.: 31763
Op Name: BLAKE PRODUCTION CO., INC.
Address: 3535 NW 58TH ST., STE 1020
OKLAHOMA CITY, OK 73112

Conductor Pipe: Size feet: \$ 107.74
Surface Casing: Size 8.625 feet: 204 250 SX
Production: Size 5.5 feet: 3315 150 SX
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2002 1:00 PM

Plug Co. License No.: 31763 Plug Co. Name: BLAKE PRODUCTION CO., INC.

Proposal Rcvd. from: RICK SCHURZ Company: BLAKE PRODUCTION CO., INC. Phone: (785) 567-8686

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 500# hulls.
Perfs 3172'-3183'; 3133'-3143'; 3150'-3158'; 3245'-3257'; 3266'-3270'; 3192'-3196';
3105'-3109'; 3088'-3092'.
CIBP at 3100'.
Bad casing. High fluids.

Plugging Proposal Received By: PAT STAAB

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/25/2002 3:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 875' and 1475'.
Express Well Service RIH with tubing to 2900' and tagged plug.
Pulled one joint and pumped 240 sxs with 500# hulls to circulate cement to surface.
Pulled tubing and tied onto casing and pumped 50 sxs 60/40 pozmix with Max.P.S.I. 350#. S.I.P. 150#.
Backside had been squeezed and was full of cement.
Checked by visusal inspection.
Job complete.

RECEIVED
1 JUN 20 2002
06-28-02
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS LYNCH #1. ALLIED CEMENTING COMPANY-TICKET #6124.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

JUN 26 2002

INVOICED
DATE 7-8-02
INV. NO. 2003060007

Form CP-2/3

CITIES SERVICE OIL & GAS CORPORATION

36-04 -20W
NW NW NE

#1 LYNCH

site: 2 E OF LOGAN, KS
contr: UNKNOWN

city: PHILLIPS
field: SLINKER

API IOG-58476

fr	spd	drlg	card	last
date 10/19/51	date 10/20/51	comp 10/26/51	issued 12/14/51	revised 08/24/88

ELV: 1943 KB SMP

tops.....	depth/datum
DAK SD.....	.540 +1403
B/DAK SD.....	.850 +1093
CHEY SD.....	.930 +1013
B/CHEY SD.....	.960 +983
ANH.....	.1455 +488
B/ANH.....	.1490 +453
LANS.....	.3105 -1162
BKC.....	.3314 -1371
PBTD.....	.3081 -1138
RTD.....	.3320 -1377

IP status:
 OIL; P 129 BO & 10 BWPD, LKC 3081-3266 OA,
 INFO RELEASED: 8/24/88 - ADDED WELL INFO
 CSG: 8-5/8" 205 / 150 SX, 5-1/2" 3313 / 150 SX
 NO CORES OR DSTS
 MICT - CO, PF (LKC) 3081-3266 OA (6 ZNS), TRTMNT
 NOT RPTD, GSO, POP, P 62 BO & 57 BW / 14 HRS, P 77
 BO & 21 BW / 24 HRS, IP P 129 BO & 10 BWPD, PHY
 POT (WELL PRODUCED UNTIL P&A 1/22/88)

COPYRIGHT 1988
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS