

4-041606

8-11 15-147-30002-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1964

SW SW NW /4 SEC. 35, 04 S, 20 W
2970 feet from S section line
4950 feet from E section line

Operator license# 6771

Lease Ross well # 1

Operator: Ozark Enterprises

County Phillips

109.46

Address: P.O. Box 128
Gainesville, MO 65655

Well total depth 3368 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 194 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 11 Month: August Year: 94

Plugging proposal received from: Steve Morrison

Company: Ozark Enterprises Phone:

Were: 4 1/2" casing set @ 3363' w/NA sxs. cmt. Perfs. @ 3216' - 3220'.
Salt @ 2300' - Anhy. @ 1450' - Dakota @ 850'. Squeeze with 280 sxs. at
2500' - 1984'. Perf. casing at 150' - circulate cement to surface.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30P.M., Day: 11, Month: August, Year: 94

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 180 sxs.
60/40 pozmix - 10% gel with 1/4# F.C. Circulated cement to surface
perf. at 150'. Max. 400#.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1994

CONSERVATION DIVISION
WICHITA, KANSAS

8-31-94

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [] and [] observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED
DATE 9-8-94
REV. NO. 41156
8-11

HO.