

4-031877

12-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,293 ⁰⁰⁻⁰⁰
100'E.of
NW NW SW /4 SEC. 25, 04 S, 20 W
2240 feet from S section line
4780 feet from E section line

Operator license# 5352

Lease Donahey well # 2

Operator: Baird Oil Company, Inc.

County Phillips

111.80

Address: P.O. Box 428
Logan, Kansas 67646

Well total depth 3440 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 214 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 2 Month: December Year: 93

Plugging proposal received from: Jim Baird (Dennis Hamel KCC)

Company: Baird Oil Company, Inc. Phone:

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Perf's at 870' and 1530' - critical control shots.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:40P.M., Day: 2, Month: December, Year: 93

Actual plugging report: 8 5/8" set @ 214' w/175 sxs. cwc. 4 1/2" set @
3440' w/250 sxs. P.B.T.D. @ 3418'. Perf's at 3188' - 3320'. Squeezed
4 1/2" w/200 sxs. cement blend with 400# hulls mixed in to Max. P.S.I.
800#. Close in P.S.I. 600#. Squeezed 8 5/8" with 50 sxs. cement blend
with 100# hulls mixed in to Max. P.S.I. 600#. Close in P.S.I. 600#.
Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X observe the plugging.

Carl Goodrow

INVOICED
DATE DEC 13 1993
INV. NO. 39498

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1993
12-10-1993
Form CP-203
CONSERVATION DIVISION
Wichita, Kansas