

4-032163

API Number: 15-039-20, 397-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

6-11

SE SE NE /4 SEC. 23, 04, 27 W
2970 feet from S section line
330 feet from E section line

Operator license# 4767

Lease: Petracek Well # 1

Operator: Ritchie Exploration, Inc.

County: Decatur

Address: 125 N. Market - Suite 1000
Wichita, Kansas 67202

Well total depth 3695 ^{120.08} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 254 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Paul's Well Service License# TAG 3118

Address: Ellis, Kansas 67665

Company to plug at: Hour: P.M. Day: 11 Month: June Year: 1996

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone: -

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Order workstring of 2 3/8" tubing.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 25 1996

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

CONSERVATION DIVISION
WICHITA, KS
6-25-96

Completed: Hour: 12:25 P.M., Day: 11, Month: June, Year: 1996

Actual plugging report: 8 5/8" set at 254' cwc with 210 sxs. 4 1/2" set at 3692' with 225 sxs. Squeezed 1695' - 2092' with 470 sxs. Hole at 1247'. PBTD 3605'. Prod. Perfs 3476' - 3620'. Ran tubing. Spotted 50 sxs cement blend with 300# hulls at 3565'. Pulled to 2550'. Spotted 50 sxs cement blend. Pulled to 1500' - circulated with 35 sxs cement blend with 200# hulls mixed in. Laid down tubing - topped off with 10 sxs. Squeezed 8 5/8" with 155 sxs. cement blend. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

OK/MB

INVOICED
DATE JUN 26 1996
INV. NO 45887