

6 031420 15039-19039-00-02 15039-005640000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1954  
SW NW SW, SEC. 25, T 4, S, R 27  
1650 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 5011

Lease Name Jennings Unit Well # 4-6

Operator: Viking Res. Inc.  
Name & Address: 105 S. Broadway  
Suite 1040  
Wichita, Ks. 67202-4224

County Decatur 114.53  
Well Total Depth 3524 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 693

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: \_\_\_\_\_ PM Day: 1 Month: August Year: 19 90

Plugging proposal received from Vernon

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: 10 3/4 set at 693 w/350 sks. 7" set at 3521 w/175 sks. Perfs 3041 - 3499.

O.H. 3521 - 24. Order 300 sks 65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co.

LaRue Water Trucks. Kelso Wireline to fish.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:00PM Day: 1 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sq 7" w/300 sks with 500 lbs. hulls mixed into max

psi 600 lbs. Close in psi 300 lb Sq annulus w/150 sks to max psi 350 . Close in psi 150 lb.s Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED I (paid) observe this plugging.

DATE 10-2-90

INV. NO. 29493

*John S.*

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

RECEIVED STATE CORPORATION COMMISSION

SEP 26 1990

CONSERVATION DIVISION Wichita, Kansas

926-90