

6 030789

PLUGGED 150397

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-039-19040-00-00

CSENW, SEC. 25, T. 4 S, R. 27 W DE

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Operator: TEXACO INC.

Name & Address Box 2420

TULSA OKLAHOMA

74102

3300 feet from S section line

3300 feet from E section line

Lease Name JENNINGS Well # UNIT TRACT 2 #3

County DECATUR 59.51

Well Total Depth TD 1831 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 640'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON License Number \_\_\_\_\_

Address OBERLIN KANSAS

Company to plug at: Hour: AM Day: 27 Month: 5 Year: 19 86

Plugging proposal received from Tom JACKSON

(company name) TEXACO INC. (phone) \_\_\_\_\_

were: 10 3/4 SET @ 640 CWC 7" SET @ 1830 CWC PERF. 1680-1780 C.H.,  
ORDER 250 SX. ECONOLITE 65/35POZ 10% GEL 2% DICEL 6 SX. HULLS  
HALLIBURTON CNT. CO. HARVE WATER TRUCK.

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:53 AM Day: 27 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT TIE ON TO 7" MIX & Pump Down 7" w/ 250 SX.  
CEMENT SLURRY + 6SX. HULLS MIXED IN TIE ON TO BACKSIDE  
(ANNULUS) PRESSURED UP TO 650# CLOSED IN. BACKSIDE  
WOULD NOT TAKE CEMENT. MAX. PSI ON 7" = 650# CLOSED  
IN @ 200# PLUG COMPLETE.

RECEIVED

Remarks: ELEV. 2500 DK 1000 (If additional description is necessary, use BACK of this form.)

10-5-86

INVOICED

DATE 10-3-86

OCT 3 1986

Signed Carl Goodnow (TECHNICIAN)

INV. NO. 15102