

15-039-00566-00-~~01~~
01

6 031426

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NE SW NE SEC. 25, T 4 S, R 27 W/E
3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Jennings Unit Well # 3-1

Operator: Viking Resources Inc.

County Decatur

Name & Address 105 S. Broadway Suite 1040

Well Total Depth 3616 117.52 feet

Wichita, Ks. 67202-4224

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 678

Abandoned Oil Well Gas Well Input Well xx SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks

Company to plug at: Hour: PM Day: 12 Month: Sept Year: 19 90

Plugging proposal received from Millard

(company name) Kelso (phone)

were: 10 3/4 set at 678 w/575 sks cwc 7" set at 3611 w/225 sks. PBTB 3608.

Perfs 3189 - 3534. Order sand common cement. Pull pipe. Order 250 sks 65/35 poz10% gel,
500-lbs. hulls. Allied Cement Co. Larue water trucks. Ran Kelso wireline to fish thru
Black Magic.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 3:00PM Day: 12 Month: sept Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3130 w/7 sks common cement on sand w/

bailer. Recovered 800 of 7" with shots from 1400. Sq 10 3/4 w/125 sks cement blend
w/300 lbs. hulls mixed into max psi 900 lbs. Close in psi 900 lbs. Blew off head.
Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
10-3-90
OCT 3 1990

Remarks:

INVOICED

additional description is necessary, use BACK of this form.

I (did / did not) observe this plugging.

DATE 10-8-90

INV. NO. 29581

Carl S.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow