

9-12
API NUMBER 15-039-00606-00-02
1952

To: 6 031425
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SE, SEC. 25, T 4 S, R 27 W/E
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Jennings Unit Well # 6-1

Operator: Viking Res. Inc.

County Decatur 112.06

Name & Address 105 S. Broadway Suite 1040

Well Total Depth 3448 feet

Wichita, Ks. 67202-4224

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 275

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 12 Month: Sept Year: 19 90

Plugging proposal received from Millard

(company name) Kelso (phone)

were: 10 3/4 set at 275 cwc w/250 sks. 7" casing set at 3488 w/175 sks.

PBTD 3415. Perf 3028 - 3333. Order sand and common cement. Pull pipe, order 300 sks 65/35 poz 10 gal. 500 lbs. hulls. Allied Cement Co. LaRue Water Truck. Ran Kelso Wireline to fish through Black Magic.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30PM Day: 12 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 2975 w/7 sks common cement on sand w/bailer.

Recovered 930 7" casing, shots from 1400. Squeezed 10 3/4 w/300 sks cement blend with 500 lbs. hulls mixed into max psi 500 lbs. Close in psi 300 lbs. plug complete.

Remarks: (If additional description is necessary, use BACK of form.)

RECEIVED
STATE CORPORATION COMMISSION
09-26-90
SEP 26 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-2-90

INV. NO. 29495

Phil S.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow