

9-8

4-032258

E-08,1900-02

15-039-00593-0000

API Number:15- - 1961

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SE NW NW /4 SEC. 25, 04, 27 W  
4290 feet from S section line  
4290 feet from E section line

Operator license# 5011

Lease: Jennings Unit Well # 1-2

Operator: Viking Resources, Inc.

County: Decatur 116.68

Address: 105 S. Broadway - Suite #1040  
Wichita, Kansas 67202

Well total depth 3590 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 328 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 8 Month: September Year: 1997

Plugging proposal received from: Mike Brown

Company: Viking Resources, Inc. Phone: -

Were: Order 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 17 1997

09-17-97

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 4:00 P.M., Day: 8 Month: September, Year: 1997

Actual plugging report: 8 5/8" set at 328' w/225 sxs cwc. 4 1/2" set at 3589' w/1025 sxs. cwc. Prod. Perfs 3025' - 3546'. PBTB 3564'. Squeezed 4 1/2" with 160 sxs cement blend with 500# hulls mixed into Max. P.S.I. 600#. Locked up. Held. Tested 8 5/8" to 500# P.S.I. with 1/2 barrel - cement at surface. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED

SEP 25 1997

DATE  
INV. NO. 49114

9-8 JAN 09 1998