

2-14

6 031333

API NUMBER 15-

039-20,242 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE SW, SEC. 22, T 4 S, R 27 W/E

990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Mazanek Well # 1

Operator: Edmiston Oil Co. Inc.
Name & Address: 1260 KSBand T Bldg.
Wichita, Ks. 67202

County Decatur 126.85
Well Total Depth 3903 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 14 Month: Feb Year: 19 90

Plugging proposal received from Mays

(company name) Edmiston OIL (phone)

were: 8 5/8" set at 206' w/160 sks cwc. 4 1/2" set at 3687' w/200 sks. Perf at

3476' - 3634. Shot at 1300' for Dakota black squeeze. Tubing and rods at 1511'.

Sanded in, Tried to fish. "Couldn't. Order work string and 225 sks 65/35 poz 10% gel
2% Dixel 500# hulls. B. J. Titan Cement Co. Water Truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00PM Day: 14 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1500' circulated cement blend to surface.

Laid down tubing, squeezed 4 1/2" w/total of 125 sks cement blend w/hulls mixed into
max psi 1200#. Close in psi 1200#.

Squeezed 8 5/8" annulus w/100 sks cement blend to max psi 200#. Close in psi 200#.

Plug complete.

Remarks: FEB 23 1990 2-23-90
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

DATE 2-26-90

INV. NO. 27563