

3-25

52

4-031675

15-039-20251-00-00

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -  
S2 SW NE /4 SEC. 36, 04 S, 27 W  
2970 feet from S section line  
1980 feet from E section line

Operator license# 5042 Lease Gaumer well # A-5

Operator: Edmiston Oil Company, Inc. County Decatur

Address: 125 N. Market Well total depth 3650 feet  
#1260 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 244 feet

118.62

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Services License# -

Address: Oakley, Kansas

Company to plug at: Hour: P.M. Day: 25 Month: March Year: 92

Plugging proposal received from: Dale May

Company: Edmiston Oil Company, Inc. Phone:           

Were: Order 325 sxs. 65/35 pozmix - 10% gel. - 500# hulls.  
Perf. 3483' - 3530'.  
Shots 1150' - 2065'.  
Hole open to produce perfs with wireline.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 1:30P.M., Day: 25, Month: March, Year: 92

Actual plugging report: 8 5/8" set @ 244' w/185 sx. 4 1/2" set @ 3649'  
w/200 sx. Squeezed 4 1/2" w/225 sx. cement blend w/500# hulls mixed  
in to max. P.S.I. 600 #. Close in P.S.I. 300 #. Squeezed 8 5/8" w/100  
sx. to max. P.S.I. 400 #. Close in P.S.I. 200 #. Plug complete.

Rec'd  
4-4-92

Remarks: Condition of casing(in hole):GOOD X BAD     Anhy.plug:YES 2065 NO      
Bottom plug(in place):YES    , CALC    , NO     Dakota plug:YES X, NO      
Plugged through TUBING    , CASING    . Elevation: 2538 GL

I did not observe the plugging. Carl Goodrow

DATE 4-22-92  
INV. NO. 34975

(agent)  
Form CP-2/3

100