

6 030753

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,592-00-00

NEESE, SEC. 32, T 4 S, R 29 (W)

990 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name PROSCH Well # 1

Operator: F&M OIL Co. INC.

County DECATUR 142.19

Name & Address 422 UNION CENTER

Well Total Depth 4375 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 329'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: PM Day: 9 Month: 6 Year: 19 86

Plugging proposal received from TONY

(company name) KELSO CASING. (phone) _____

were: 8 5/8 @ 329' w/260SX 4 1/2 @ 4153 w/100SX. PBD 4093' PERF 3955'-4031

ORDER SAND & COM. CMT. SHOOT & PULL PIPE - ORDER 200SX. ECONALITE
CMT. 5SX. HULLS HALLIBURTON CMT. CO. LARGE WATER.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:PM Day: 9 Month: 6 Year: 19 86

ACTUAL PLUGGING REPORT SAND TO 3900' w/4SX. COMCMT. ON SAND w/BAILER.

SHOT @ 2530 2378 2007 1814 1600' & RECOVERED 1600' OF 4 1/2"

TIE ON TO 8 5/8 MIX & PUMP 3SX. HULLS 200 SX. CMT. MIX. + 2SX. HULLS.

MAX. PSI 300# CLOSE W 150# PLUG. COMP.

13
6-13-86

Remarks: _____

STATE CORPORATION COMMISSION

6-16-86

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUN 18 1986

INV. NO. 14129

6-9

JUN 16 1986
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)