

3-25  
4-031673

15-039-20221-00-00

SB  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -

SW NE SE /4 SEC. 36, 04 S, 27 W  
1650 feet from S section line  
990 feet from E section line

Operator license# 5042

Lease Gaumer well # C-1

Operator: Edmiston Oil Company, Inc.

County Decatur

Address: 125 N. Market  
#1260  
Wichita, Kansas 67202

Well total depth 3640 feet 118.30  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4Inch @ 224 feet  
w/160 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: B.J. Services License# -

Address: Oakley, Kansas

Company to plug at: Hour: A.M. Day: 25 Month: March Year: 92

Plugging proposal received from: Dale May

Company: Edmiston Oil Company, Inc. Phone:                     

Were: Order 325 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Perf. 3431' - 3588'.  
Shots 1150' - 2065'.  
Hole open to produce perf's.

RECEIVED  
STATE CORPORATION COMMISSION

APR 08 1992

4-8-92

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ Wichita, Kansas ], None [     ]

Completed: Hour: 10:30A.M., Day: 25, Month: March, Year: 92

Actual plugging report: 8 5/8" set @ 224' w/160 sx. 4 1/2" set @ 3639'  
w/200 sx. Squeezed 4 1/2" w/200 sx. cement blend w/500# hulls mixed  
in to. Max. P.S.I. 500#. Close in P.S.I. 300#. Squeezed 10 3/4" w/125  
sx. to max. P.S.I. 300 #. Close in P.S.I. 150#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES 2025 NO      
Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 2522 GL    

I did [ X ] / did not [     ] observe the plugging.

Carl Goodrow

DATE 4-22-92

INV. NO. 34972

(agent)