

15-03a-00571-00-00

To: **6 031423**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1953  
NW NE NW SEC. 36, T 4 S, R 27 W/E  
4950 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011  
Operator: Viking Res.  
Name & Address 105 S. Broadway Suite 1040  
Wichita, Ks. 67202-4224

Lease Name Jennins Unit Well # 7-1  
County Decatur 117.32  
Well Total Depth 3610 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 709

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: AM Day: 12 Month: Sept Year: 19 90

Plugging proposal received from Millard  
(company name) Kelso (phone) \_\_\_\_\_

were: 10 3/4 set at 709 w/325 sks cwc 7" set at 3607 w/175 sks. PBTD 3510.

Perf 3125 - 3580 O.H. 3607 -10. Order sand common cement. Pull pipe. Order 250 sks  
65/35 poz 10% gel, 500 lbs. hulls. Allied Cement Co. LaRue Water Trucks.

Ran Kelso wireline to anhydrite.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:00 AM Day: 12 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3075 w/7 sks common cement on sand  
w/bailer. Rec 1100 of 7" w/shots from 2000. Sq 10 3/4 w/250 sks cement blend w/500 lbs.  
hulls mixed into max psi 400 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form)

INVOICED observe this plugging.

DATE 10-8-90  
INV. NO. 29582

*G.S.*

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow