

10-29-87

6 030992

API NUMBER 15-039-20268-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SE, SEC. 26, T 4 S, R 27 W/E

2310 feet from S section line

990 feet from E section line

Lease Name Petrasek Well # B-1

County Decatur 117.23

Well Total Depth 3607 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 287

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Operator: Edmiston Oil Co. Inc.

Name & Address 1260 KSB Bldg.

Wichita, Kansas 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Oakley, Kansas

Company to plug at: Hour: PM Day: 29 Month: Oct. Year: 19 87

Plugging proposal received from Darrel

(company name) Edmiston Oil (phone) _____

were: 8 5/8" set at 287' w/235 sks cwc 4 1/2" set at 3606' w/225 sks. Well was squeezed

several times. Perf at 2010' and 1300' for block squeeze production. Perfs

3125' -, 3522' PBD 3548'. Order 250 sks Thrifty Mix 65/35 Poz 10% Gel 2%

Dicel. B. J. Titan Cement Blend, 5 sks Hulls. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00Pm Day: 29 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/150 sks Cement Blend w/4 sks Hulls

mixed in. Max Psi 1200#. Close in Psi 800#. Squeeze backside w/100 sks

Cement Blend w/1 sk Hulls mixed in. Max Psi 300#. Close in Psi 150#. Plug

complete.

RECEIVED
STATE CORPORATION COMMISSION
11-30-87
NOV 30 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did) (did not) observe this plugging.

DATE 12-4-87

INV. NO. 19095

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow