

To: **STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202**

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers Inc. of Ks.
Name & Address: Box 8647
Wichita, Ks. 67208

API NUMBER 15-15 039-20,117-00-00

NE NE NE SEC. 26, T 4 S, R 27 W/E
4950 feet from S section line
330 feet from E section line

Lease Name Petracek Well # 1
County Decatur 117.32
Well Total Depth 3610 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 282 w/225

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Oil producers Inc of Ks. License Number 8061
Address _____

Company to plug at: Hour: 10:00 Day: 31 Month: July Year: 19 90

Plugging proposal received from Brad Siroky

(company name) Oil Producers Inc. of Ks. (phone) _____

were: 5 1/2 casing set at 3667 w/190 sks. Sq at 1605 w/300 sks.
Perf 3144 to 3594.

Plugging Proposal Received by Gil Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 Day: 31 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Hooked up to annulus would not take cement.

Pumped 50 sks 60/40 poz 8% gel followed w/250 sks 60/40 poz. 8% gel mixed w/500 lbs.
hulls. Max pres 150 lbs. Shjut in. No pres. Check August 1, 1990. Cement to surf.

Remarks: Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED (If necessary observe this plugging.)

DATE: 8-28-90
INV. NO. 28138

Gib. S

Signed Gilbert Balthazor
(TECHNICIAN)
Gil Balthazor

Dec 18-24-90