

11-23

86  
R

6- 100445

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-153-20,784-0000

C SW SE /4 SEC. 15, 04 S, 31 W  
20 660 feet from S section line  
1980 feet from E section line

Operator license# 30676

Lease Achilies well #15-34

Operator: Pioneer Oil & Gas

County Rawlins 147.87

Address: 6925 Union Park Cenetr  
Suite 145  
Midvale, Utah 84047

Well total depth 4550 feet  
Conductor Pipe:      inch @      feet  
Surface pipe 8 5/8 Inch @ 261 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day:      Month:      Year:     

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling phone:     

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2680 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1920 feet " 100 " Mousehole:      sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " Wiper plug & 10 sx.

12-18-91  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 18 1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 8:00 am, Day: 23, Month: November, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2920 GL, Anhydrite depth: 2682 - 2715 feet  
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO  
Plugged through drill pipe: YES  
Did NOT penetrate Arbuckle, cemented by Allied

[      ] did not [ X ] observe the plugging.

David K. Wann  
David K. Wann P.I.R.T. II  
(agent)

INVOICED  
DATE 1-7-92  
INV. NO. 34227

Gib. S.