

4- 070997

7-7

10/ R

15-039-20124-0000

D-15,292

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -  
C NE NE /4 SEC. 26, 04 S, 27 W  
4620 feet from S section line  
660 feet from E section line

Operator license# 8061 Lease Petracek well #2SWD

Operator: Oil Producers Inc. of Kans. County Decatur

Address: P.O. Box 8647 Well total depth 2020 feet <sup>65.65</sup>  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 170 feet

Aband. oil well    , Gas well    , Input well    , SWD X, D & A    

Plugging contractor: Halliburton Service - Murfin Cement License#    -   

Address: Oberlin, Kansas - Hill City, Kansas

Company to plug at: Hour: P.M. Day: 7 Month: July Year: 92

Plugging proposal received from: Brad Siroky

Company: Oil Producers Inc. of Kansas Phone: 316-681-0231

Were: 8 5/8" 170' S.P. cwc. w/200 sx. 4 1/2" casing set @ 2020'  
w/450 sx. cement. 4 1/2" casing cwc. to surface. Proposal 50 sx.  
class A. common on bottom and 250 sx. of 65/35 pozmix - 6% gel. Spot  
with tubing, load 4 1/2" casing with cement also pressure 4 1/2" x 8 5/8"  
annulus with cement.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 1:30P.M., Day: 7, Month: July, Year: 92

Actual plugging report: Oil Producers ordered 50 sx. class A common  
cement and 250 sxs. of 65/35 pozmix - 6% gel. and 3 sx. hulls. Spotted  
and displaced all cement through tubing. Ran 2 3/8" tubing to 1520'.  
Spotted 50 sx. class A and displaced. Pulled tubing to 1200'. Spotted  
78 sx. pozmix cement circulated out of 4 1/2" casing. Squeezed 4 1/2"  
casing with 5 sx. cement. Max. pressure 600 P.S.I. Shut in @ 600 P.S.I.  
Squeezed 4 1/2" x 8 5/8" annulus with 0 cement. Max. pressure 1000 P.S.I.  
Shut in @ 300 P.S.I.

Remarks: Cemented by Halliburton Cement.

Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES NR NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation:     GL

I did X / did not [     ] observe the plugging.

*Marion J. Schmidt*  
(agent)

**INVOICED**  
DATE 7-29-92  
INV. NO. 35826

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1992  
07-24-92

CONSERVATION DIVISION  
Wichita, Kansas