

15-039-00572-00-02 4-5-91

NOC 362

6 031524

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1961

SE NE NW, SEC. 36, T 4, S, R 27 W&E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Jennings Unit Well # 7-2

Operator: Viking Resources Inc.

County Decatur 117.22

Name & Address 105 S. Broadway Suite 1040

Well Total Depth 3607 feet

Wichita, Ks. 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 700

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated E - 8190

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 5 Month: April Year: 19 91

Plugging proposal received from Monte

(company name) Kelso (phone)

were: 10 3/4 set at 700 w/350 sks cwc 7" set at 3601 w/175 sks.

Perfs 3259 - 3576. OH. 3601 - 07. Order sand and common cement.

RECEIVED STATE CORPORATION COMMISSION Pull pipe. Order 225 sks 65/35 poz 10% gel 500 lbs. hulls. Halliburton Cement Co. Larue Water Trucks.

04-26-91
APR 26 1991

CONSERVATION DIVISION Wichita, Kansas Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45PM Day: 5 Month: April Year: 19 91

ACTUAL PLUGGING REPORT

Sand back to 3200 w/7 sks common cement on sand w/bailer recovered 1000 of 7" casing w/shots at 2010, 1800, 1600, 1400,

1200. Loaded 7 casing w/75 sks cement blend. Laid down 7" casing.. Hole full

of cement and black magic Sq 10 3/4 w/total of 200 sks cement blend

w/500 lbs hulls mixed in to max psi 350 lbs. Close in psi 150 lbs.

Plug complete.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-13-91
INV. NO. 31807

H.S.

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)