

6 030877

6-2-87 15-039-20110-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 9-16-69

SE NE NE, SEC. 36, T 4 S, R 27 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Tacha Well # 2 SWD

Operator: Edmiston Oil Co. Inc.

County Decatur 57.20

Name &

Address 1260 KSB Bldg.

Well Total Depth 1760 feet

Wichita, Kansas 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Poe Well Service License Number \_\_\_\_\_

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 2 Month: 7 Year: 19 86

Plugging proposal received from Bill Saling

(company name) Edmiston Oil Co. (phone) \_\_\_\_\_

were: 8 5/8 at 230 with 200 sk. 5 1/2 at 1642' with 250 sks. Perf. at 1231' with 125 sk casing was bad and effort was made to clean out and reline. While drilling out old casing the bit drilled out of original hole. They had drilled to 1230' and trying to reenter they couldn't get below 580' with bit. Ordered 135 sk 65/35 poz 10% gel 2% dicel econolite.

Halliburton Services Plugging Proposal Received by Carl Goodrow Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: PM Day: 2 Month: 6 Year: 19 86

ACTUAL PLUGGING REPORT Load hole through tubing with econolite lay down tubing- annulus circulated - tie on to 5 1/2 and 8 5/8 and squeezed with 135 sx cmt mix. Max PSI 500 # Close in 150 # PSI Plug Complete.

REC-1111  
STATE CORPORATION COMMISSION  
JUN 25 1987  
6-25-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED** (If applicable) observe this plugging.

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow

DATE 6-25-87

INV. NO. 17351 JUL 3 0 1987