

4-5

6 031233

API NUMBER 15-153-00028-00-02

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NW NW, SEC. 23, T. 4 S, R. 33 WAE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9269

Lease Name Ruda Well # 2

Operator: Ruda Exploration
Name & Address Route 1 Box 87

County Rawlins 146.02

Atwood, Kansas 67730

Well Total Depth 4493 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated E-16,115

Plugging Contractor Production Drilling License Number 153

Address Hays, Ks.

Company to plug at: Hour: PM Day: 5 Month: April Year: 19 89

Plugging proposal received from Ken Ruda

(company name) Ruda Exploration (phone) _____

were: 8 5/8" set at 450' w/225 sks. 4 1/2" set at 4350' w/250 PBD 4350.

Perf 3986 - 4087. Order 250 sks 65/35 Poz 8% Gel 300# Hulls. Allied Cement Co.

Murfin Water Truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45PM Day: 5 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Pump cement through tubing at 1316' - circulated

cement. Laid down tubing. Squeezed 4 1/2" casing w/200 sks 600# Hulls to max psi 300.

Close in psi 150#. Squeezed 8 5/8" w/10 sks to max psi 700#. Close in psi 700#. Plug

complete.

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1989

Remarks: _____
(If additional description is necessary, use BACK of this report.)

INVOICED
serve this plugging.

DATE 4-24-89

[Signature]

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

INV. NO. 24479