

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20085-00-01
Spot: CNENE Sec/Twnshp/Rge: 23-4S-27W
550 feet from N Section Line, 550 feet from E Section Line
Lease/Unit Name: PETRACEK OWWO Well Number: 4
County: DECATUR Total Vertical Depth: 3925 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet: \$127.56
Surface Casing: Size 8.625 feet: 282 200 SX CMT
Production: Size 4.5 feet: 3920 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/07/2001 1:00 PM
Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.
Proposal Rcvd. from: PETER J. FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/07/2001 1:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

PBTD at 3854'. D.V. at 2072'.
Plugged 4 1/2" casing with 205 sxs 60/40 pozmix - 10% gel - 400# hulls.
Max. P.S.I. 800#. S.I.P. 700#.
No cement displaced down annulus.
Instant pressure P.S.I. 300#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

DEC 04 2001

KCC WICHITA

INVOICED

DATE 12-5-01

INV. NO. 2002061030

Form CP-2/3


NOV 16 2001

REPLACEMENT CARD

A. SCOTT RITCHIE
 125 N. MARKET, #950 WICHITA, KS. 67202
 #4 PETRACEK 'OWWO' C NE NE
 23-4-27W
 CONTR MURFIN DRILLING COMPANY CTY DECATUR

GEOL _____ FIELD JENNINGS

ELV 2558 KB SPD 10/26/84 CARD ISSUED 5/16/85 IP P 15 BO & 60 BWPD
 DRLG COMP 10/27/84 LKC 3483-3647 OA
 API 15-039-20,085-A



LOG	Tops	Depth/Datum
*ANH	2086+ 472
*B/ANH	2118+ 440
TARK	3160- 602
HOW	3251- 693
TOP	3267- 709
HEEB	3440- 882
TOR	3472- 914
LANS	3482- 924
BKC	3676-1118
PENN SD	3850-1292
ARB	3880-1322
LTD&RTD	3925-1367
*SAMPLE TOPS		

OLD INFO: OPERATOR WAS MURFIN DRILLING CO. & NADEL & GUSSMAN, #1 PETRACEK, SPD 4/17/69, SET 8 5/8 " 241 / 200SX, DRLG COMP 10/27/84, COMP AS D&A/ARB (CARD ISSUED 5/8/69), CONTR: MURFIN DRILLING, CONTR: BILL IVERSON
 DST (1) 3164-3236 (TARK) / OP 90", REC 70' M, SIP 1033# / 30" - 1002# / 60", NO FP
 DST (2) 3243-3260 (HOW) / OP 90", REC 55' WM, SIP 1054# / 30" - 1044# / 60", FP 23-52#
 DST (3) 3314-3318 (TOP) / OP 90", REC 20' SLI OCM, 180' M, SIP 962# / 30" - 962# / 60", FP 31-109#
 DST (4) 3363-3408 (TOP) / OP 90", REC 300' WM, 708' SW, SIP 1044# / 30" - 1097# / 30", FP 52-495#
 DST (5) 3447-3516 (TOR) / OP 90", REC 240' OIL SPKD M, 1460' SLI OCSW, SIP 1086# / 30" - 1075# / 60", FP 42-864#
 CORRECTION: 6/12/86 - CORRECTED ELEV - WAS 2555 KB
 NOTE: 5/16/85 - GRADED ELEV ON OWWO WAS 2559 KB, 2554 GL

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)

A. SCOTT RITCHIE #4 PETRACEK 'OWWO' 23-4-27W
 C NE NE

DST (6) 3562-3568 (LKC) / OP 90", REC 1350' SW, SIP 1170# / 30" - 1160# / 60", FP 31-643#
 DST (7) 3581-3688 (LKC) / OP 90", REC 200' GIP, 360' OCM, 180' MDY OIL, 120' OCW, 900' OCM & WTR, SIP 1160# / 30" - 1160# / 60", FP 94-727#
 DST (8) 3576-3604 (LKC, W / STR PKR) / OP 90", REC 1360' SW, SIP 1191# / 30" - 1191 # / 60", FP 31-685#
 DST (9) 3603-3688 (LKC) / OP 90", REC 180' OIL & WCM, 180' OCW, 960' W, SIP 1181# / 30" - 1181# / 60", FP 105-748#
 NEW INFO: FR 10/8/84, RE-ENTERED 10/26/84, WSH DWN TO 3925' TD, SET 4 1/2 " 3920 / 225SX, MICT -CO, PF (LKC) 3644-3647, AC 1600 GAL, SWB LD, GSD, PF (LKC) 3483-3486, W / 2 SPF, AC 1600 GAL, SWB DWN, GSD, T&R, POP, P 15 BO & 60 BWPD, 3/5/85