

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20022-00-01
Spot: CSWNE Sec/Twnshp/Rge: 23-4S-27W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: PETRACEK OWWO Well Number: 5
County: DECATUR Total Vertical Depth: 3960 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 242 200 SX CMT \$128.70
Production: Size 4.5 feet: 3914 300 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E23643.1 Date/Time to Plug: 11/07/2001 11:00 AM

Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.

Proposal Rcvd. from: PETER J. FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/07/2001 12:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

PBTD at 3650'. D.V. at 2049'.
Plugged 4 1/2" casing with 210 sxs 60/40 pozmix - 10% gel - 400# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
No cement displaced down annulus.
Instant pressure P.S.I. 200#.

Remarks: LEASE ALSO KNOWN AS PETRACEK #1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

DEC 04 2001

KCC WICHITA

INVOICED

DATE 12-5-01

INV. NO. 2002061030

Form CP-2/3

NOV 19 2001

REPLACEMENT CARD

A. SCOTT RITCHIE
125 N. MARKET, #950
WICHITA, KS. 67202


#5 PETRACEK 'OWWO'

23-4-27W
C SW NE

CONTR MURFIN DRILLING COMPANY CTY DECATUR

GEOL _____ FIELD JENNINGS

ELV 2556 KB SPD 12/18/84 CARD ISSUED 2/14/85 IP SWDW
LKC 3489-3660 OA



API 15-039-20,022-A

LOG	Tops	Depth/Datum
ANH	2084+	472
BURL	3226	670
HOW	3252	696
TOP	3270	714
HEEB	3444	888
TOR	3474	918
LANS	3488	932
BKC	3682	1126
CHER	3828	1272
SEVERY SD	3856	1300
REW ARB	3884	1328
ARB	3897	1341
ORTD	3931	1375
OLTD	3935	1379
PBTD	3650	1094
DDTD	3960	1404

OLD INFO: OPERATOR WAS J. C. GRAVES & J. N. CHAMPLIN, #1 PETRACEK, SPD 9/5/67, SET 8 5/8 " 241 / 175SX, COMP AS D&A/ARB (CARD ISSUED 10/5/67), CONTR: GRAVES DRILLING, GEOL: BENTON BROOKS

DST (1) 3296-3320 (TOP) / OP 60", REC 300' M, W/SPTS BLK OIL, SIP 1099# / 30" - 1037# / 30", FP 73-148#

DST (2) 3498-3565 (LKC) / OP 60", REC 110' M, SIP 1151# / 30" - 1099# / 30", FP 73-84#

DST (3) 3565-3600 (LKC) / OP 60", REC 170' MW, SIP 1254# / 30" - 1192# / 30", FP 63-95#

NEW INFO: FR 11/20/84, RE-ENTERED 12/18/84, WSH DWN ORTD, DD 3960 TD, SET 4 1/2 " 3785 / 230SX, MICT - CO, PF (LKC) 3654-3660 3629-3632, 3489-3492, 3596-3600, 3514-3518, W / 2 SPF, AC 5050 GAL, SWB DWN, SWDW - INJECTION RATE SATISFACTORY, 1/11/85

CORRECTION: 6/12/86 - CORRECTED ELEV - WAS 2550 KB

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS