

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-19008-00-01
Spot: SENESE Sec/Twnshp/Rge: 26-4S-27W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: PETRASEK B Well Number: 1
County: DECATUR Total Vertical Depth: 2025 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

Conductor Pipe: Size feet: 65.81
Surface Casing: Size 8.625 feet: 259
Production: Size 4.5 feet: 2024 225 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D17184.0 Date/Time to Plug: 08/23/2002 10:00 AM

Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.

Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Plugging Method: Ordered out 235 sxs 60/40 pozmix - 10% gel - 800# hulls.
Casing leaks at 533'; 1317' - 1348'; 1485'.
Fluid Level 300'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/23/2002 12:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1665'.
Allied pumped 50 sxs 60/40 pozmix - 10% gel with 250# hulls.
Pulled tubing to 680'.
Allied pumped 50 sxs with 250# hulls - cement circulated.
PTOH. Squeezed with 50 sxs with 200# hulls.
Max. P.S.I. 600#. S.I.P. 200#.
Hooked up to backside - pumped 30 sxs with 100# hulls.
Blew hole in 8 5/8" below head.

RECEIVED

AUG 27 2002
08-27-02
KCC WICHITA

Remarks: ORIGINALLY KNOWN AS NELLANS ESTATE #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

8-28-02

INV. NO.

2003060458

AUG 26 2002

EDMISTON OIL CO. #1 PETRASEK "B" SWDW 26-4-27W
 801 FIRST NATL. BLDG., WICHITA, KS. SE NE SE
 CONTR CO. TOOLS CTY DECATUR

GEOL _____ FIELD JENNINGS

E 2510 RB CM 7/2/73 ^{CARD}ISSUED 8/2/73 IP SWDW/CEDAR HILLS
 1748-98

API

TOPS	DEPTH	DATUM
TOR	3240	- 730
HEFB	3371	- 861
LANS	3410	- 900
TD	3525	-1015
LOG		
B FT HAYS	540	+1970
CEDAR HILLS	1585	+ 925
ANHY	2006	+ 504
TD	2025	+ 485

OLD INFO: WAS PEEL-HARDMAN #1 NELLANS EST
 8"250, 5"3525, PF 3496-3500 AC 1000, NS
 PB 3480, PF 3450-60 A. 1500, NS, PB 3210
 PF 3180-87 AC 500 SWB 3 BWPH

NEW INFO: WASHED DWN TO 2025; 4 1/2" 2024/
 225SX, PF 100/1748-98(CEDAR HILLS) DID NOT
 TAKE WATER SWB 5HRS 84BPM INJ RATE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS