

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20088-00-02
Spot: E2NWNE Sec/Twnshp/Rge: 36-4S-27W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: TACHA Well Number: 1
County: DECATUR Total Vertical Depth: 3600 feet

Operator License No.: 5042
Operator Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 251
Production: Size 4.5 feet: 3599
Liner: Size _____ feet: 117.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/23/00
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Plugging Method: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/23/2000 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 251' w/225 sxs cwc. 4 1/2" set at 3599' w/150 sxs.
Prod. Perfs 3410' - 3514'. Sanded in to 1900'.
Shot off tubing at 1900'. Displaced 45 sxs cement with 300# hulls.
Pulled tubing to 900' - circulated cement.
Lay down tubing. Squeezed 4 1/2" with total 250 sxs cement blend with 500# hulls mixed into Max. P.S.I. 150#. Held.
Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 150#. Held.

Remarks: ALLIED CEMENT COMPANY.

Plugged through: TBG

District: 04

Signed Carl Goodrow

(TECHNICIAN) RECEIVED
STATE CORPORATION COMMISSION

1102
INVOICED
DATE 10/31/00
INV. NO. 2001060909

OCT 30 2000 Form CP-2/3
10 30-2000
CONSERVATION DIVISION
Wichita, Kansas

OCT 25 2000

