

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

NOV 17 1981
11-17-81
CONSERVATION DIVISION
Wichita Kansas

API NUMBER 15-039-20,550 -00-00 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER Joseph C. Taylor

ADDRESS 459 S. Alcott, Denver, CO 80219

LEASE (FARM NAME) Petracek WELL NO. 1

WELL LOCATION NE NE NW SEC. 23 TWP. 4S RGE. 27W (EAST) (WEST)

COUNTY Decatur TOTAL DEPTH 3686' FIELD NAME _____

OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:00 p.m., November 23, 1981.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Albert Unruh ADDRESS Box 176, Chase, Kansas 67524

PLUGGING CONTRACTOR KELSO Casing Pulling LICENSE NO. _____

ADDRESS Box 176, Chase, Kansas 67524

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Joseph C. Taylor

ADDRESS 459 S. Alcott, Denver, CO 80219

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OR ACTING AGENT.

SIGNED: _____

Jack B. Wharton
APPLICANT OR ACTING AGENT
Vice President, A.L. Abercrombie, Inc.

DATE: November 16, 1981

80

CONTRACTOR'S WELL LOG

OPERATOR: Joseph C. Taylor
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: PETRACEK #1
 LOCATION: NE NE NW, Section 23-4S-27W
 Decatur County, Kansas
 SPUD DATE: 12/10/80
 COMPLETION DATE: 12/19/80

0	287	Shale & Sand
287	940	Shale
940	2115	Shale & Sand
2115	2149	Anhydrite
2149	2205	Shale & Sand
2205	2912	Shale
2912	2950	Shale, Lime, Iron
2950	3165	Shale & Lime
3165	3686	Lime
	3686	RTD

Spud @ 5:15 p.m., 12/10/80. Drilled 287' hole. Ran 7 jts. of 20# 8 5/8" casing (tally 278.30) Set @ 286'. Cemented with 200 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 2:30 a.m., 12/11/80.

T.D. 3686'. Ran 88 jts. of 4 1/2" - 10 1/2# casing (tally 3699.18) Set @ 3685' K.B. Ran 25 bbl. chemical flush. Ran 50 sx. of 50-50 posmix, 2% gel, 12 1/2# gilsinite per sack. Followed with 150 sx. of common salt saturated. Plug was down @ 12:45 p.m., 12/18/80.

SAMPLE TOPS:

Anhydrite	2115'	
B/Anhydrite	2149'	
Tarkid	3183'	(-612)
Howard	3275'	(-704)
Heebner	3468'	(-897)
Toronto	3496'	(-925)
Lansing	3570'	(-939)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 17 1980
 11-17-81
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the PETRACEK #1 NE NE NW, Section 23-4S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 30th day of December, 1980.



Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public

State of Kansas



15-039-20550-00-00

JOHN CARLIN
C. LOUX
WANE T ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202
January 11, 1982

Extended Authority
5-18-82 aw

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Petracek
Description	NE NE NW
Section	23-4-27W
County	Decatur
Total Depth	3686'
Plugging Contractor	Kelso Casing Pulling

Joseph C. Taylor
459 S. Alcott
Denver Colorado 80219

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,



DELBERT J. COSTA, Administrator

Mr. Carl Goodrow, Box 189, Penokee, Ks., 67659, (913)674-5593

is hereby assigned to supervise the plugging of the above named well.

NOTE: If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.

THIS PERMIT

APR 11 1982

EXPIRES