

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy) 15-039-20244-00-00

API NUMBER 10-6-72 15-039-20,244-00-00 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Edmiston Oil Company OPERATORS LICENSE NO. 5042

ADDRESS 1260 KSB Bldg., Wichita, Kansas 67202 PHONE # (316) 265-5241

LEASE (FARM) Beers WELL NO. 1 WELL LOCATION NE NE SE COUNTY Decatur

SEC. 23 TWP. 4 RGE. 27 or TOTAL DEPTH 3662 PLUG BACK TD 3655

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 205 CEMENTED WITH 160 SACKS

CASING SIZE 4-1/2 SET AT 3662 CEMENTED WITH 225 SACKS

PERFORATED AT 3610, 3578, 3505, 3496, 3237, 3210, 3190, 3545, 3538

CONDITION OF WELL: GOOD _____ POOR CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL (Casing corroded at 2640', out of the hole below that point. Squeezed hole in casing at 1811' w/500 sxs. 10-17-85). Plug @ 2644 with 25 sxs., pull casing from approximately 1200 ft. plug at 1000' w/100 sxs. plug at 205' with 40 sxs. Plug @ 40' with 10 sxs. (If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? unknown
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be arranged

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

W.O. Saling 7-8-86 PHONE # (316) 564-2639

ADDRESS Route 3, Box 103 Bend, KS 67530

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050 6/87

ADDRESS Box 347 Chase, Kansas 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: John M. Calla
(Operator or Agent)

DATE: July 7, 1986

6

15-039-20244-00-00

GREAT GUNS

R. A. Guard Log

FILE NO. COLLARS ADDED	COMPANY <u>E. K. EDMISTON OIL COMPANY</u>	
	WELL <u>BEERS NO. 1</u>	
	FIELD _____	
	COUNTY <u>DECATUR</u>	STATE <u>KANSAS</u>
LOCATION: <u>NE-NE-SE</u>		OTHER SERVICES
SEC <u>23</u> TWP <u>4S</u> RGE <u>27W</u>		

Permanent Datum <u>GROUND LEVEL</u>	Elev. <u>2542</u>	Elevations: KB <u>2547</u>
Log Measured from <u>KELLY BUSHING 5 Ft. Above Permanent Datum</u>		DF <u>2544</u>
Drilling Measured from <u>KELLY BUSHING</u>		GL <u>2542</u>

Date	GAMMA	NEUTRON	GUARD	CALIPER
10-15-72				
Run No.	ONE	ONE	ONE	ONE
Depth-Driller	3662	3662	3662	3662
Depth-Logger	3663	3663	3663	3663
Bottom Logged Interval	3654	3662	3658	3651
Top Logged Interval	000	000	3000	3000
Casing - Driller	@	@	8 5/8	@
Casing-Logger				
RH Size			7 7/8	
Type Fluid in Hole			CHEMICAL MUD	
Density and Viscosity			8.8 45	
pH and Fluid Loss		cc	8.5 8.3 cc	cc
Source of Sample			PTF	
Rm @ Meas. Temp.	@ °F	@ °F	.17 @ 70 °F	@ °F
Rmf @ Meas. Temp.	@ °F	@ °F	.14 @ 70 °F	@ °F
Rmc @ Meas. Temp.	@ °F	@ °F	.34 @ 70 °F	@ °F
Source of Rmf and Rmc			CHARITS	
Rm @ BHT	@ °F	@ °F	.18 @ 110 °F	@ °F
Time Since Circ.	STATE CORPORATION COMMISSION		2 HOURS	
Max. Rec. Temp. Deg. F.		@ °F	110 °F	@ °F
Equip. No. and Location	JUL 8 1956		14 HAYS	
Recorded By	CONSERVATION DIVISION Wichita, Kansas		MUNDAY	
Witnessed By			MR. IVERSON	

CORRELATION LOG R/W 10-26-70

REMARKS



15-039-20244-00-00

JOHN CARLIN Governor
MICHAEL LENNEN Chairman
MARGALEE WRIGHT Commissioner
KEITH R. HENLEY Commissioner
JUDITH A. McCONNELL Executive Secretary
BRIAN J. MOHNE General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

Extension THIS NOTICE
THIS NOTICE OCT 8 1986
APR 5 '87 EXPIRES
EXPIRES
90-Days

July 8, 1986
WELL PLUGGING NOTICE

Beers #1
NE NE SE
Sec. 23-4S-27W
Decatur County

Edmiston Oil Company, Inc.
1260 KSB Building
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please contact the district office to review your suggested method of plugging

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).