

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15,039-20,221-00-00 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Edmiston Oil Company, Inc. OPERATOR'S LICENSE NO. 5042 *6-92*

ADDRESS 125 N. Market, #1260, Wichita, KS 67202 PHONE # (316) 265-5241

LEASE (FARM) GAUMER "C" WELL NO. 1 WELL LOCATION SW NE SE COUNTY DC

SEC. 36 TWP. 4S RGE. 27 ~~(E)~~ or (W) TOTAL DEPTH 3640 PLUG BACK TD 3639

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 225 CEMENTED WITH 160 SACKS

CASING SIZE 4 1/2" SET AT 3639 CEMENTED WITH 200 SACKS

PERFORATED AT 3470-76, 3520-22, 3586-88

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off from total depth to 3450'. Set cement plug.

Sand off to base of Anhydrite. Perf at base of Anhydrite and set 50' cement plug.

Sand off to 40' and cement to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED?
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN After February 24, 1992

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dale May PHONE # (316) 792-6924

ADDRESS P. O. Bxo 232, Great Bend, KS 67530

PLUGGING CONTRACTOR BJ-Titan LICENSE NO. _____

ADDRESS P. O. Box 69, Hays, KS 67601 PHONE # (913) 625-3019

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *John M. Call*
(Operator or Agent)

DATE: February 19, 1992

(4)

ORIGINAL

DRILLER'S LOG

COMPANY: Edmiston Oil Company and
R. W. Shields
801 First National Bank Building
Wichita, Kansas 67202

ROTARY DRILLING COMMENCED: October 26, 1971

ROTARY DRILLING COMPLETED: November 5, 1971

WELL NAME: GAUMER "C" #1

LOCATION: SW NE SE Sec. 36-4S-27W
Decatur County, Kansas

CONTRACTOR: E. K. Edmiston Drilling Co., Inc.
801 First National Bank Building
Wichita, Kansas 67202

CASING RECORD: Set 224' of 10-3/4" surface pipe
w/160 sacks cement
Ran 4 1/2" casing @ 3639' w/200 sacks

L O G

Measurements from top of Kelly Bushing (Elevation 2537 K.B.)

Sand and Shale	0 - 242
Shale and Shells	1075
Shale	2036
Anhydrite	2068
Shale	2362
Lime	2588
Shale	2798
Lime and Shale	3223
Lime	3405
Shale and Lime	3512
Lime	3532
Lime and Shale	3580
Lime	3640 R.T.D.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 20 1992
CONSERVATION DIVISION
WICHITA, KS


The undersigned, E. K. Edmiston, President of E. K. Edmiston Drilling Co., Inc., hereby certifies on behalf of said company, that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

E. K. Edmiston

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

BE IT REMEMBERED that on this 9th day of November, 1971, before me, the undersigned, a Notary Public within and for the County and State aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument on behalf of E. K. Edmiston Drilling Co., Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.



Marilyn E. Fox, Notary Public

15-039-20221-00-00



RADIATION-GUARD LOG

COMPANY R. W. SHIELDS
 WELL GAUMER "C" # 1
 FIELD SOUTHEAST JENNINGS
 County DECATUR State KANSAS

COMPANY R. W. SHIELDS
 WELL GAUMER "C" # 1
 FIELD SOUTHEAST JENNINGS
 COUNTY DECATUR STATE KANSAS

Location SW-NE-SE Other Services: NONE
 Sec. 36 Twp 4S Rge 27W
 FEB 20 1992
 WICHITA DIVISION

Permanent Datum GROUND LEVEL Elev.: K.B. 252
 Log Measured From KELLY BUSHING Fr. Above Perm. Datum D.F. 252
 Drilling Measured From KELLY BUSHING G.L. 252

Date	11-4-71	11-4-71	11-4-71	59682 WUB
Run No.	ONE	GAMMA	NEUTRON	GUARD
Depth-Driller	3640'	3640'	3640'	
Depth-Welex	3641'	3641'	3641'	
Btm. Log Inter.	3633'	3641'	3634'	
Top Log Inter.	0'	0'	3000'	
Casing-Driller	@	@	10.3' @ 224'	@
Casing-Welex				
Bit Size			7-7/8"	
Type Fluid in Hole			CHEMICAL MUD	
Dens. Visc.			10.3 59	
pH Fluid Loss	ml	ml	9.5 14 ml	m
Source of Sample			FLO LINE	
R _{int} @ Meas. Temp.	@ °F	@ °F	.86 @ 74 °F	@ °F
R _{int} @ Meas. Temp.	@ °F	@ °F	.64 @ 74 °F	@ °F
R _{int} @ Meas. Temp.	@ °F	@ °F	1.12 @ 74 °F	@ °F
Source R _{int} R _{int}			MEAS	
R _{int} @ BHT	@ °F	@ °F	.61 @ 107 °F	@ °F
Time Since Circ.			TWO HOURS	
Max. Rec. Temp.	°F @	°F @	107 °F @ BH	°F @
Equip. Location	74341 HAYS			
Recorded By	J. DAVIS			
Witnessed By	MR. IVERSON			

K. G. S. LIBRARY

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

15-039-20221-0000

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 24, 1992

Edmiston Oil Company Inc
125 N Market 1260
Wichita KS 67202

Gaumer C 1
API 15-039-20,221
SW NE SE
Sec. 36-04-27W
Decatur County

Dear Operator:

This letter is to notify you, that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200