

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-039-20,115-06-00 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Edmiston Oil Company, Inc. OPERATOR'S LICENSE NO. 5042 *6-82*

ADDRESS 125 N. Market #1260, Wichita, KS 67202 PHONE # (316) 265-5241

LEASE (FARM) TACHA WELL NO. 3 WELL LOCATION S/2 NE NE COUNTY DC

SEC. 36 TWP. 4S RGE. 27 ~~(E)~~ or (W) TOTAL DEPTH 3650 PLUG BACK TD 3645

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 225 CEMENTED WITH 200 SACKS

CASING SIZE 4 1/2" SET AT 3645 CEMENTED WITH 175 SACKS

PERFORATED AT 3237, 3240, 3188, 3495-99, 3526-30, 3540-44, 3573-77

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off from total depth to 3450'. Set cement plug.

Sand off to base of Anhydrite. Perf. at base of Anhydrite and set 50' cement plug.

Sand off to 40' and cement to surface.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN After February 24, 1992

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dale May **RECEIVED** (316) 792-6924

ADDRESS P. O. Box 232, Great Bend, KS 67530 KANSAS CORPORATION COMMISSION

PLUGGING CONTRACTOR BJ-Titan Services **FEB 20 1992** LICENSE NO. 2-2092

ADDRESS P. O. Box 69, Hays, KS 67601 CONSERVATION DIVISION (913) 625-3019  
WICHITA, KS

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.**

SIGNED: *Dale May*  
(Operator or Agent)

DATE: February 19, 1992

(4)

15-039-20115-00-00



# RADIOACTIVITY LOG

COMPANY R. W. SHIELDS  
 WELL TACHA # 3  
 FIELD JENNINGS  
 County DECATUR State KANS.

COMPANY R. W. SHIELDS  
 WELL TACHA # 3  
 FIELD JENNINGS  
 COUNTY DECATUR STATE KANSAS

Property of  
 Kansas Geological Society  
 540 Petroleum Bldg.  
 Wichita, Kansas

Location C - S 1/2 NE-NE  
 Sec. 36 Twp. 4S Rge. 27W  
22W

Other Services:  
 NONE

Permanent Datum GROUND LEVEL Elev. 2559'  
 Log Measured from 5' ABOVE GROUND LEVEL  
 Drilling Measured From KELLY BUSHING

Elev.: K.B. 2564  
 D.F. 2561  
 G.L. 2559

Date	9-16-69	9-16-69	57807
Run No.	ONE	ONE	WIB
Type Log	<del>GAMMA</del> RECEIVED	NEUTRON	
Depth-Driller	3615'	3613'	
Depth-Welex	3615'	3615'	
Bottom Logged Interval	3607'	3615'	
Top Logged Interval	3000'	3000'	
Type Fluid in Hole	DRY		
Salinity, PPM Cl.			
Density			
Level	DRY		
Max. rec. temp., deg. F.	106°		
Operating Rig Time	ONE HOUR		
Recorded By	J. DAVIS		
Witnessed by	MR. SHIELDS &	MR. ECKEL	

RUN No.	BORE-HOLE RECORD				CASING RECORD			
	Bit	From	To		Size	Wgt.	From	To

K. G. S. LIBRARY  
 OBSERVATION DIVISION  
 WICHITA, KS

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

15-039-20115-00-00

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 24, 1992

Edmiston Oil Company Inc  
125 N Market 1260  
Wichita KS 67202

Tacha 3  
API 15-039-20,115  
S2 NE NE  
Sec. 36-04-27W  
Decatur County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

  
David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director

200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200