



15-137-00738-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1972  
05-24-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Henry Well No. 4

Location: CN/2-NW Sec. 2 Twp. 4 Rge. (E)(W) 24

County: Norton Total Depth 3764' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

306'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3763'--5 1/2" Production casing, cemented on bottom with 100 Sx. Top of perforations @ 3614'.

Sand well back to 3600' and set 5Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*R. L. Nichols*

Conservation Division Agent