



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-137-00144-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1972  
05-24-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Theodore Gore,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Henry Well No. 1

Location: NE-NE-NW Sec. 2 Twp. 4 Rge. (E)(W) 24

County: Norton Total Depth 3737' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

264'--8 5/8" Surface casing, cement circulated with 135 Sx.

3734'--5 1/2" Production casing cemented with 100 Sx. on bottom. No plug back nor perforations indicated.

Sand well back to 3700' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squee e well with 5 Sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent