



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1973
6-13-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. L. C. Brau of E. K. Edmiston Drlg. Co., Inc has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Edmiston Oil Company,

Complete Address: 801 1st National Bank Bldg., Wichita, Kansas.

Lease Name: Beers Well No. 2 - A

Location: C S/2 NE SE Sec. 23 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3664' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Brau was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 200 Sx. cement.
Top of Kakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent