



15-039-20249-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 4 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. L. C. Brau of E. K. Edmiston Drlg. Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Edmiston Oil Company, Inc.

Complete Address: 801 First National Bank Bldg., Wichita, Kansas.

Lease Name: Mazanek Well No. 2

Location: S/2-NE-<sup>SW</sup>~~NW~~ Sec. 22 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 1800' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole X

Mr. Brau was instructed to plug the well as follows:

206'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1050'. Lost circulation on bottom was unable to  
regain.

Push plug to 1425', sand back from 1425' to 1350' and displace 150 Cu. Ft.  
cement thru DP. Let cement set to check then finish plugging hole.

Very truly yours,

M. S. D. J. J. J.  
Conservation Division Agent