



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)Rec'd  
02-05-73J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this  
date requested permission to plug the following described well:Mr. Kelso guarantees payment of the plugging fee.Operator's full Name: Thunderbird Drilling, Incorporated,Complete Address: Box #18407, Wichita, Kansas.Lease Name: Skubal Well No. 2Location: SE-NE-NE Sec. 35 Twp. 4 Rge. (E)(W) 27County: Decatur Total Depth 3889' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Kelso was instructed to plug the well as follows:330'--8 5/8" Surface casing cement circulated.3688'--5 1/2" Production casing cemented on bottom with 175 Sx. No plug  
back indicated. Top perforation @ 3174'.Push plug to 3190', sand back from 3190' to 3150' and set 5 Sx. cement  
with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls,  
25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent